



278 WORKS
PENRHOS RETAIL PARK
HOLYHEAD
ANGLESEY

DELIVERY TEAM

Hollingsworth Bros
UK Ltd

CLIENT

ANWYL HOMES

VALUE

£300,000

CONSULTANTS

MONO Civil Design Consultant

DETAILS

The main aim of this project was to provide a new access road for the proposed Anwyl Homes development. This would involve the installation of a new roundabout, creating a new access into the Anwyl development site, new footpaths to both sides of the site entrance, new street lighting, new signage, new island beacons, resurfacing of existing road/footpaths including building up levels for new tie in and all traffic/pedestrian management. Hollingsworth Bros also undertook the installation of all drainage and street lighting duct/draw pits. All works were carried out in accordance with current Highways agency specifications and under the supervision of Anglesey County Council Highways department. Hollingsworth Bros were responsible for dealing with all relevant licences/road openings etc, and also liaising with utility providers regarding diversions.

Construction Specification/Details

The new Roundabout & Traffic Islands were constructed using traditional half Battered kerbs forming the main radius of the roundabout & Traffic Islands. The roundabout runover area was then surfaced with Red Textureflex, the centre of the roundabout was finished with tarmac and the relevant signage installed.





The Main Carriageway was constructed using traditional surfacing methods and to Highways and IOACC specifications, this element of work was carried out on behalf of Hollingsworth Bros by Hogan Bros surfacing.

All earthworks, drainage, ducting, kerbing and formations were carried out by our own team of skilled workforce. All of whom are trained to current New Roads And Streetworks Act, including supervision level.

New Street lighting and signage was installed by IOACC approved contractor Gwynydd Street Lighting under the guidance of H Bros management. A number of new lighting columns has to be installed along with illuminated bollards to the traffic islands.

PROJECT CHALLENGES

The 278 works were undertaken in close proximity to a school so during the construction works care had to be taken to allow continuous pedestrian access especially taking into account a large number of the pedestrian were children. All works were phased in such a way to minimize any risk to pedestrians. We had a road sweeper visiting the site regularly to make sure the road were kept free of muck created by the main housing development site.

PROGRAMME.

All Hollingsworth Bros Works were completed on programme.

CLIENT SATISFACTION

All works were carried out with zero complaints from local residents/businesses. We had the following feedback from IOACC *“It been a pleasure to work with you all as a team it has been an eye open experience for me to see how professional you are as a company”*.

Hollingsworth Bros (UK) Ltd
St. Ives Way
Engineer Park
Sandycroft
Flintshire CH5 2QS

T: 01244 539922

F: 01244 538504

www.hollingsworthgroup.co.uk

